


Construction Sequencing BMP

Limit Disturbance BMPs



Overview

Schedule construction shifts so that only those needed are on the construction site at a time. This is done with the goal of minimizing the erosion and control sediment.



Design

Simply need to consider a vast array of construction considerations, such as: when materials can be delivered, where materials can be stored on site, ect.

Do not stockpile materials and parking equipment under a canopy of trees, this can compact soils and kill the trees.

Siting

Construction sequencing might be used throughout any site large enough that some cleared areas of the site would be “open” without construction activity for more than a month during the rainy season from September to early July.

Maintenance

The plan may need to be changed/updated if the current plan is not providing sufficient erosion prevention and sediment control. Otherwise this BMP is low maintenance.

Cost

This is a low-cost measure because it takes a limited amount of the contractor’s time to provide a written response for coordinating construction activities and management practices.

