



April 8, 2024

**PROJECT: City of Cottage Grove
South R Street Right-of-Way Improvements**

ADDENDUM #2

Branch Engineering Inc. Project No. 22-001A



EXPIRES: 6/30/2025

The following clarifications and revisions for the above-referenced project are hereby incorporated by addendum to the previously issued bid documents.

Contractor Question - Is the soil preparation described on sheet L.0 (excavate to 12" below finish grade, till 8" depth then place 12" topsoil) apply to the planter strip between the curb and sidewalk? Is that excavation paid by Cyd under bid item #7 general excavation? Clarification: Yes, it is to apply to the planter strip between the sidewalk and curb. Soil preparation outside of the vegetated rain garden and stormwater planter are to be paid for by bid item #38 Site Restoration, Permanent Seeding and Topsoil.

End of Addendum #2